

PROJECT NAME: Poplar Street Drainage Improvements

MCADAMS PROJECT NO.: KND21001

DATE: July 11, 2024

ITEM NO.	DESCRIPTION	SPEC SECTION	PAY ITEMS PARAGRAPH	QUANTITY	UNIT	UNIT PRICE	TOTAL
1	Construction Surveying (3% of Base Bid)	NCDOT 801	NCDOT 801-3	1	LS		
2	Mobilization (7% of Base Bid)	NCDOT 800	NCDOT 800-2	1	LS		
3	Traffic Control Measure (5% of Base Bid)	ToK 2.07	NCDOT 1105-6	1	LS		
4	Clearing and Grubbing (10% of Base Bid)	31 25 00	NCDOT 200-8	1	LS		
5	2"-3" Surge Stone or Railroad Ballast for Construction Entrance	ToK 2.04	NCDOT 1610-4	29	TN		
6	Silt Fence/Tree Protection	31 25 00	NCDOT 1605-5	1951	LF		
7	Typical Excavation	ToK 2.05	-	1302	CY		
8	Rock Blasting/Chiseling	ToK 2.05b	NCDOT 220-4	1651	CY		
9	Haul Off	ToK 2.05a	NCDOT 255-7	864	CY		
10	Grading (Fine/Comprehensive)	31 05 00	NCDOT 226-3; 500-5	2941	SY		
11	Import for Dam and Topsoil Use	ToK 2.05d	NCDOT 230-5	3447	TN		
12	Reused Class I Riprap	ToK 5.04	NCDOT 876-4	36	TN		
13	Reused Class A Riprap	ToK 5.04	NCDOT 876-5	7	TN		
14	Reused Class B Riprap	ToK 5.04	NCDOT 876-6	3	TN		
15	#57 Stone for Velocity Dissipator	ToK 5.04	NCDOT 876-4	10	TN		
16	Geotextile Fabric	31 25 00	NCDOT 270-4	171	SY		
17	Cast-In-Place Concrete Weir Wall	03 30 00	NCDOT 420-21	5	CY		
18	8"-Diameter PVC Pipe	NCDOT 305	NCDOT 305-4	1	LF		
19	Seeding and Mulching	ToK 2.04b	NCDOT 1660-8	0.69	AC		
20	Sod	32 92 00	NCDOT 1664-5	2804	SY		
21	Canopy Trees	NCDOT 1670	NCDOT 1670-17	7	EA		
22	Eastern Blue Star Wetland Plants	NCDOT 1670	NCDOT 1670-17	210	EA		